

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


12-24-11W

PHILLIPS PETRO.CO.
Tretbar No. 7.

SEC.12 T.24 R.11 W
CET¹ NW NE

Total Depth. 3735' PB 3707'
Comm. 4-8-42 Comp. 6-3-42
Shot or Treated. Total 4000 Gals Acid
Contractor.
Issued. 7-25-42

County. Stafford



CASING:
13 3/8" 73'
8 5/8" 303'
5 1/2" 3711'

Elevation.

Production. Pot.2700 B.BHB

Figures Indicate Bottom of Formations.

surface formation	73
shale & sand	315
red bed shale	480
anhydrite	500
shale gy, shells	1050
salt	1255
shale & shells	1665
sand chert	1708
sand, shale, shells, chert	2003
shale, lime, lime shells	2841
shale & lime	2926
lime	3024
lime & chert	3071
lime	3195
shale	3217
lime & shale	3423
lime	3461
lime & shale	3554
lime	3628
shale & lime	3690
sand	3710
lime Viola	3718
lime	3735
Total Depth.	

Tops:

Anhydrite not picked
Misener sand 3690
Viola lime 3710

Cored 3692-99 rec 7' sand w/SSO
Cored 3699-3709 rec.sand from
99-06 w/sat. from 3702-06
Cored 3709-18 1st foot shale
Top Viola 3710' w/good saturation.
Cored 3734-35
made 2 BOPH at 3735

Plugged back to 3707
Perf. opposite Misener sand
from 3701¹ to 3706