

Plotted  
 13-24-11  
 988


STANOLIND OIL & GAS CO.  
 O. J. Hartnett No. 5.

SEC. 13 T. 24 R. 11W  
 NE SE NW  
 990'N SL 2310'E WL

County. Stafford

Total Depth. 3791'  
 Comm. 1-10-39 Comp. 1-30-39  
 Shot or Treated.  
 Contractor.  
 Issued. 3-18-39 Rotary 3777  
 Cable 3791

MAR 18 1939



CASING:  
 10 3/4" 238'1"  
 7" 3773'

Elevation.

Production. Pot. 668 B.  
 No water

Figures Indicate Bottom of Formations.

sdv shale & red beds	286
sand & clay	390
rod beds & shale	790
shale & shells	1370
shale & lime	1895
lime	1980
shale & lime shells	2250
shale	2605
lime brkn	2625
shale	2700
shale & lime	2816
shale	2870
lime	3040
lime & shale	3134
lime	3180
lime & shale	3350
limo	3681
shale	3772
sand	3791
Total Depth.	

5th 39, 6th 29 Bbls., No wtr.

Misener sand 3772-3791

Core Record

Core #1 3763-3777 14' recovery	
shale green	3772
sand vory shaly w/scattered	
shows of oil	3776 1/2
sand shaly, fair porosity,	
good sh oil	3777
Core #2 3777-3780 2 1/2' recovery	
sand fine to coarse shaly,	
show oil and gas	3780
Core #3 3780-3788 8' recovery	
sand mod sft, green, shaly,	
some saturation	3782
sand mod hrd, well saturated	
oil and gas	3785
sand vory sft, good sat.	3787
sand vory sft, lean sat.	3788
Core #4 3788-3791 1' recovery	
sand hrd tight, vory lgt sh	
oil	3791

6 hr-flow test thru casing -  
 1st 47, 2nd 37, 3rd 24, 4th 42,