


14-24-11W 9.8
card made up
SEC. 14 T. 24 R. 11W
SE NE SE
1650' N SL 2317' E WL
990' S NL 330' W EL

PURE OIL CO.
John Krey No. 6.

County. Stafford

Total Depth. 3806'
Comm. 8-2-38 Comp. 9-6-38
Shot or Treated. 8 Qts. 3796-3807 OCT 8 1938
Contractor.
Issued. 10-8-38 Drilled with rotary,
drilled in with standard.



CASING:
10" 244'
7" 3784'

Elevation.

Production. Pot. 1833 B.
Flowed

Figures Indicate Bottom of Formations.

surface sand	70	lime	3680
brkn sand & red rock	130	brkn lime & shale	3783
red bed	170	sand	3803
sand & shells	210	Top Misener	3783
brkn sand & shale	240	First sh oil	3785
red rock	325	First Gas	3789
sand	340	chert	3806
red rock	420	limey sand	3808
red rock & shale	525	lime	3809
shale & shells	630		
red bed & shale	860	Note-3' correction after	
shale	1090	taking out derrick floor	
brkn salt & shale	1185	and substructure. Measure-	
salt & shale	1230	ment to be from cement mat.	
shale & lime	1245	Total Depth	3809-3806
brkn shale	1375		
edy lime	1385		
brkn sand & shale	1550	Top Misener sand corr.	3780'
shale & shells	1610		
lime	1632		
brkn lime	1790		
shale & lime	1855		
sand	1890		
lime	2245		
brkn lime & shale	2625		
brkn lime	2710		
brkn lime & shale	2773		
lime	2816		
brkn lime & shale	2943		
lime	3081		
brkn lime	3151		
lime	3228		
brkn lime	3258		
brkn lime & shale	3350		
lime	3389		
-Top Kansas City Lime	3384		
brkn lime	3403		
lime	3458		
brkn lime & shale	3500		
lime	3571		
brkn lime & shale	3606		