


Plotted
14-24-116
card made out
SEC. 14 T. 24 R. 11W
NW SE SE
1655'N SL 1650'E WL

PURE OIL CO.
John Krey No. 7.

County. Stafford

Total Depth. 3809'
Comm. 8-8-38 Comp. 9-15-38
Shot or Treated. 12 Qts 3795-3806
Contractor.
Issued. 10-15-38

OCT 15 1938



Drilled with rotary
Drilled in w/standard

CASING:

10" 264'
7" 3777'

Elevation.

Production. Pot. 2023 B.
flowed

Figures Indicate Bottom of Formations.

clay	35
sand	110
red rock	281
surface sand & shale	448
red bed	507
anthracite	528
red bed & shale	680
sdv lime & shale	740
shale & shells	1150
red bed & lime shell	1175
red bed & salt	1260
brkn lime & sand	1350
shale	1385
brkn lime & shale	1510
brkn lime	1595
sand	1620
lime	1850
sand	1880
lime	1900
sand	1925
lime	1985
brkn lime & shale	2155
lime	2233
brkn lime & shale	2575
brkn lime	2625
lime	2694
brkn lime & shale	2782
shale	2795
brkn lime	2805
lime	2840
shale & lime shell	2900
brkn lime	2921
lime	3098
brkn lime & shale	3175
lime	3260
brkn sand	3297
lime	3370
brkn lime & shale	3394
—top Lansing	3390
lime	3675
brkn lime & shale	3715
shale	3786
top Misener sand	3786
sand	3806
1st sh oil	3795

chert	3808
chert & sdv lime	3809
sdv lime	3812
3' Corr after taking out derrick floor & sub-structure	
Measurement to be from concrete mat 3812=3809	
Total Depth	3809

Top Misener sand corr. 3785