

14-24-11W Plotted
WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

card made out

PURE OIL CO.
John Krey No. 9.


SEC. 14 T. 24 R. 11W
SW NE SE
990'NSL 1654'EWL 990'SNL 992'W
EL

Total Depth. 3806' P.B.3799' Corr.
Comm. 8-29-38 Comp. 10-5-38
Shot or Treated. 5 Qts. 3784-3802
Contractor.
Issued. 10-29-38

County. Stafford

Drilled w/ rotary
Drilled w/standard

OCT 29 1938



CASING:
10" 259'
7" 3784'

Elevation.

Production. Pot. 2380 B.flowed
11,084 Ave Gas

Figures Indicate Bottom of Formations

sand & red bed	165
red bed	285
surface sand - red bed	591
red bed & shale	875
shale & shells	1513
brkn lime	1650
lime	1860
sand	1895
lime	2030
br.lime & shale	2105
sand	2115
brkn lime	2205
br. lime & shale	2415
lime	2480
br. lime & shale	2540
sdv lime	2570
lime	2583
brkn lime	2675
br. lime & shale	2785
lime	2833
br. lime & shale	2890
brkn lime	2913
lime	3052
brkn lime	3194
lime	3255
brkn sand	3285
br. lime & shale	3336
shale	3386
br. lime & shale	3397
lime(Top of Lansing 3400)	3598
br. lime & shale	3607
lime	3639
br. lime & shale	3710
shale	3783
hrd sand (Top Misener 3783)	3784
sand sft	3785
sand 1st gas show 3791	3801½
chert	3802
sand & chert	3804
chert	3806
Total Depth.	

Plugged back 3806-3802
3' corr after taking out derrick
floor and sub-structure
3802=3799 Total Depth.
Top Misener sand corr to 3780