

14-24-11W Plotted

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.,

PURE OIL CO.
John Kroy No. 12

SEC. 14 T. 24 R. 11W.
SE NW SE
1651' N of S.L.
993' E of W.L.
990' S of S.L.
1654' W of E.L.


Total Depth. 3809 P.B. 3807 equals 3804.
Comm. 10-17-38 Comp. 12-13-38
Shot or Treated. 5 qts 3789-3807
Contractor.
Issued. 1-7-39

Rotary and Cable.

CASING.

10" 261'
7" 3788'

County. Stafford.



Elevation.

Production. Pot. 4022 B.
flowed after shot.

Figures Indicate Bottom of Formations.

sand	120	brokon limo and sand	3321
shale and red rock	288	shale and limo shells	3365
red bed	350	brokon limo and shale	3407
red bed and sand	515	shale	3420
anhydrite	565	limo slight show gas	3450
red bed and shale	690	3420-40	
shale and salt	1238	limo and shale	3472
sdv shale	1390	limo	3551
shale and limo shells	1512	shells and limo	3557
brokon limo	1740	limo	3607
limo	1805	limo and shale	3707
shale	1850	brokon limo and shale	3730
limo	1870	shale	3787
sdv limo	1905	sand oil & gas 3791	3807
limo	1935	sand and chert	3809
limo and shale	2005	Total Depth.	
limo	2080		
brokon limo and shale	2169	Plugged back	
limo	2235		
brokon limo and shale	2270	3809 - 3807 water	
brokon limo	2354	3807 equals 3804 cor. T.D. after	
limo and shale	2406	taking out derrick floor and	
limo shells	2433	sub structuro.	
limo and shale	2459		
brokon limo	2497	Top Kansas City limo 3392.	
shale and limo shells	2570		
limo	2618	Top Misenor sand corrected to 3784	
brokon limo	2681		
limo and shale	2700		
sdv shale	2717		
limo	2722		
brokon limo	2866		
shale	2890		
brokon limo and shale	2931		
limo	3024		
brokon limo	3073		
limo	3198		
brokon limo	3218		
brokon limo & shale	3230		
limo and shale	3264		
brokon sand	3290		