

14-24-11W

STANOLIND OIL & GAS CO.
 B. McComb No. 4.

SEC. 14 T.24 R.11W
 CE $\frac{1}{2}$ NW SW
 1980' N SL 990' E $\frac{1}{4}$ SW $\frac{1}{4}$

Total Depth. 3832'
 Comm. 3-18-40 Comp. 4-5-40
 Shot or Treated.
 Contractor.
 Issued. 6-29-40 Rotary O-3832

County. Stafford



CASING:
 10 $\frac{3}{4}$ " 245'
 7" 3791'9"

Elevation.

Production. Pumped
 Pot. 299 B.
 12% Wtr

Figures Indicate Bottom of Formations.

cellar	9
sand	123
red bed	274
red bed & shells	700
shale gy	769
red bed & shale	872
shale	1094
salt	1169
shale	1267
shale & shells	1454
lime	1591
anhydrite & shale	1674
brkn shale blue & lime	1722
shale	1730
lime	1750
shale & shells	1785
sand & lime	1806
shale sdy	1918
lime	2091
shale	2141
shale & lime	2241
shale & shells	2293
lime	2335
shale & lime	2371
lime	2557
shale & lime	2654
lime	2750
shale & lime	2798
lime	2845
shale & lime	2882
shale & sand	2896
lime	3268
shale green	3297
shale	3400
shale & lime	3419
lime	3509
shale brkn & lime	3536
lime	3544
lime brkn	3593
lime	3700
shale	3730
shale & lime	3758
shale	3790
lime	3813
sand	3816

lime	3817
dolomite lime	3829
shale, dolomite	3830
dolomite lime	3832
Total Depth.	

Top Unconformity 3789
 Viola 3816-3832

Swabbed 41.72 oil, 3.28 wtr from
 btm-pumped potential of 299 B0-
 12% Wtr