

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

14-249.81.92
PLOTTED
Copy made

STANOLIND OIL & GAS CO.
M. Volker No. 2-B.

SEC. 14 T. 24 R. 11W.
SE SW SW
330' N of S.L. 990' E of W.L.

Total Depth. 3827
Comm. 4-6-38 Comp. 5-6-38
Shot or Treated.
Contractor.
Issued. 7-9-38

County Stafford.

CASING.

Rotary 3802 $\frac{1}{2}$
Cable 3827

JUL 9 1938

13" 266' 7" 3799.3

Elevation.

Production. Pot. 1716 B.
no wtr.

Figures Indicate Bottom of Formations.

sand surface clay	65
surface clay	200
sand	240
red rock	268
red bed	571
shale	964
shale salt and shells	1286
salt and shells	1486
shale and shells	1584
lime	1874
broken lime	2014
shale	2082
broken lime	2137
broken lime and sticky shale	2185
lime	2228
broken lime and shale	2313
broken lime	2467
broken lime and shale	2522
sticky shale	2543
broken lime	2552
shale	2791
broken lime and shale	2882
broken lime	3068
broken lime and lime	3130
broken lime	3210
lime	3252
lime and shale streaks	3300
broken lime	3374
shale	3412
Top of Lansing 3412	
lime	3644
lime hard dense	3685
broken lime and shale	3723
lime and shale breaks	3747
shale	3790
shale green	3800

Top of Unconformity	3800 $\frac{1}{2}$
chert	3800-3801
sand	3802 $\frac{1}{2}$
Cable tools.	
lime	3804
core No. 1 5/5 Rec.	3804-3809
shale grey and lime	
Core No. 2 5/5 Rec.	
lime grey	3809-3814
core No. 3 0/3 Rec.	
lime	3815
sand Misener	3817
Core No. 4 7/7 Rec.	3823
sand dark soft	
cherty lime mud soft	
whitish in color	3824
Core No. 5	
cherty lime grey no sat.	3827
Total Depth.	

Top Lansing lime 3412.
Misener zone 3800 $\frac{1}{2}$ -3827

flowed 89 bbls per hr in 3 hour test
no water