

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Plotted JS

15-24-11W

STANOLIND OIL & GAS CO.
U.G. Ferris "A" No. 5.

SEC. 15 T. 24 R. 11W
CWL NW SE
2004' N SL 330' E WL SE $\frac{1}{4}$

Total Depth. 3824'
Comm. 6-1-41 Comp. 6-26-41
Shot or Treated.
Contractor.

County. Stafford

Issued. 8-30-41 Rotary O-3801
Cable 3801-24

CASING:

8 5/8" 256' 9" Cem.
5 1/2" 3785' Cem.

Elevation.

Production. Pot. 100 B. Phy.
No wtr

Figures Indicate Bottom of Formations.

cellar	5
sand & clay	100
sand & red bed	235
red bed	540
anhydrite	575
shale & red bed	665
shale & shells	1120
salt	1375
shale & shells	1595
lime	1655
shale & lime	1825
lime brkn	1930
lime	2025
lime brkn	2075
shale & lime	2265
shale & shells	2360
shale	2485
shale & shells	2655
shale & lime	2920
lime	3105
shale & lime	3190
lime	3280
shale & lime	3425
lime	3505
chert & lime	3515
lime	3600
lime & shale	3635
shale & shells	3670
lime	3735
shale & lime	3785
chert & lime	3789
lime & dolomite	3801
limestone & chert	3803 $\frac{1}{2}$
dolomite & chert	3806
sdv lime & phosphate	3808
sand, limy phosphate	3814
dolomite & chert	3816
dolomite	3818
dolomite & chert	3821
dolomite	3824
Total Depth.	

Misener 3783-3798
Viola 3815-24

Swab test from bottom ave.
3 BOPH for 3 hrs
Swab test from bottom ave.
3 $\frac{1}{2}$ BOPH, no wtr, for 3 hrs
Acidized-will not flow -
Swab test f.b. ave. 12 BOPH
no wtr for 3 hrs.
Physical potential 100 BO,
no wtr. Casing pumped 33 B
oil in 3 hrs.

