

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 412 Union National Bk Bldg., Wichita, Kansas

*Plotted.  
E.M.*


15-24-11W

STANOLIND OIL & GAS CO.  
 U. G. Ferris "A" No. 6.

SEC.15 T.24 R.11W  
 CW  $\frac{1}{2}$  SE SE  
 660'N SL 1650'E WL SE  $\frac{1}{4}$

Total Depth. 3832'  
 Comm. 6-14-41 Comp. 7-10-41  
 Shot or Treated.  
 Contractor.  
 Issued. 9-27-41 Rotary O-3821  
 Cable 3821-32

County. Stafford



CASING:  
 8 5/8" 239'9" Cem.  
 5 1/2" 3807'1" Cem.

Elevation.

Production. Pot.1593 B.

Figures Indicate Bottom of Formations. No wtr

cellar	4'11"
sand & clay	160
red bed	536
anhydrite	577
shale & shells	1065
salt & shale	1170
shale & shells	1470
lime brkn	1980
shale	2215
lime brkn	2240
shale	2280
shale & lime shells	2380
shale	2460
lime brkn	2510
shale & lime shells	2665
lime brkn	2735
shale & lime shells	2875
lime brkn	2895
lime	3320
shale & shells	3365
shale	3405
lime	3725
shale & shells	3760
shale	3794
shale & lime	3804
lime, chert, dolomite	3821
dolomite	3826
lime & dolomite	3828
lime	3829
lime & shale	3832
Total Depth.	

Misener 3798-3819  
 Viola 3819-3832

Swab test ave. 8 BOPH, no wtr  
 for 8 hrs. Acidized w/3000  
 Gals.  
 Flow test thru 1" choke 30 BPH  
 for 3 hrs  
 Flow test thru 1" choke ave.  
 30 BOPH for 4 hrs

Potential 1593 BO, no wtr,  
 thru 1" choke 81 Bbls. in 4 hrs