


STANOLIND OIL & GAS CO.
Marjie Ethel Kirkpatrick No. 3.

SEC.15 T.24 R.11W
CWL NE NW
1980'N SL 1815'E WL NW $\frac{1}{4}$

County. Stafford

Total Depth. 3827'
Comm. 5-12-41 Comp. 5-29-41
Shot or Treated.
Contractor.
Issued. 8-23-41 Rotary O-3827

CASING:
8 5/8" 261'3" Cem.
5 1/2" 3820' Cem.



Elevation.

Production. Pot. 9700 B.
No wtr

Figures Indicate Bottom of Formations.

cellar	5'3"
clay & sand	40
sand & red bed	270
red bed	540
anhydrite	582
shale & shells	1145
shale & lime	1415
salt & shale	1545
lime brkn	1645
shale & lime	1735
lime brkn	1915
lime brkn & shale	1980
lime brkn	2135
shale & lime	2365
lime	2400
shale & lime	2485
shale & shells	2645
lime brkn	2685
lime brkn & shale	2775
shale & lime	2840
lime	2900
shale	2915
lime	3295
lime & shale	3415
lime	3470
lime & chert	3530
lime	3595
lime & shale	3710
chert	3715
shale & lime	3735
shale	3817
limo & dolomite	3819
chert & dolomite	3827
Total Depth.	

Viola limo 3817-27

Flow test thru csg average
23 BOPH, no wtr
Flow test thru one inch choke
average 54 BOPH for 3 hrs,

no wtr
BHPEP 9700 Bbls., no wtr
Flowed 146 Bbls. oil in 4 hrs.