

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

15-24-11W
886

STANOLIND OIL & GAS CO.
Marjie Ethel Kirkpatrick No. 4.

SEC.15 T.24 R.11W
CEL NW NW
1980'N SL 990'E WL NW $\frac{1}{4}$

County. Stafford


Total Depth. 3835'

Comm. 7-3-41 Comp. 7-18-41

Shot or Treated.

Contractor.

Issued. 9-27-41 Rotary O-3835



CASING:

8 5/8" 268' Cem.

5 1/2" 3826' Cem.

Elevation.

Production. Corr.Pot.3294 B.

Figures Indicate Bottom of Formations.

cellar	5
shale & red bed	285
red bed	540
anhydrite	570
shale	1055
shale & salt	1160
shale & shells	1475
lime brkn	1975
lime	2035
shale & lime shells	2080
shale & shells	2170
lime brkn & shale	2240
lime & shale	2340
shale & shells	2520
shale	2590
shale & shells	2670
lime brkn	2790
shale	2815
lime brkn	2995
lime	3240
lime brkn & shale	3300
shale	3380
shale & lime	3450
lime	3730
shale	3825
lime & chert	3828
dolomite & chert	3835
Total Depth.	

Viola 3825-35

Swb test from btm averaged 14
BOPH, no wtr for 5 hrs
Acidized - flowing test thru
1" choke averaged 46 BOPH,
no wtr for 2 hrs
Potential 3310 BO, no wtr,
flowing thru 1" choke, 1/2
open, flowed 112 BO in 4 hrs
Corrected potential 3294 BO.