

G. E. Jameson
23-24-11W

STANOLIND OIL & GAS CO.
U. G. Ferris No. 3-B.

SEC. 23 T. 24 R. 11W
SE NE NW
1650' N SL 2310' E WL

County. Stafford

Total Depth. 3811'


Comm. 3-16-38 Comp. 4-11-38

Shot or Treated.

Contractor.

Issued. 5-7-38 Rotary 3791
Cable 3811

MAY 7 1938



CASING:

10³/₄" 255'
7 " 3789'

Elevation.

Production. Pot. 1735 B.

Figures Indicate Bottom of Formations.

red bed	75
sand & shale	305
red bed	525
lime	555
shale & sand	1070
brkn lime & shale	1375
lime & shale	1540
brkn lime & shale	1755
lime	1813
brkn lime & shale	2410
shale & lime shells	2610
shale & lime	2685
shale & lime shells	2750
brkn lime shale	2860
lime & shale	2945
lime	3075
shale	3190
brkn lime	3250
shale & lime	3375
brkn lime	3440
lime	3555
Top Lansing 3400	
lime & shale	3610
lime	3640
shale	3650
brkn lime	3700
lime	3743
shale	3790
chert	3791

Misener Zone 3790-3811

Three-hr test 1st hr 102 B.
2nd hr 58 B.
3rd hr 65 B.

Top Chert 3790 Top Sand 3791

Base of Kinderhook 3790

Cable Tools

Core #1 4/8' recovery	
sand coarse saturated	3797
Core #2 4/4' recovery	
sand coarse saturated	3801
Core #3 5/5' recovery	
sand coarse saturated	3806
Core #4 4/5' recovery	
sand coarse saturated	3809
sand fine slightly sat.	3810
sdv lime hrd dry	3811
Total Depth.	

Handwritten notes:
3811 / 3791 = 120
3791 / 3743 = 102
3743 / 3700 = 102