

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

23-24-11W

STANOLIND OIL & GAS CO.
U. G. Ferris No. 7-B.

SEC. 23 T. 24 R. 11W
NWc NW
2310' N SL 330' E WL

Total Depth. 3810'

Comm. 1-24-39

Comp. 2-8-39

Shot or Treated. 2000 Gals. 3810


Contractor.

Issued. 3-25-39

Rotary 3810

MAR 25 1939

County. Stafford



CASING:

103/4"

258'7"

7"

3802'

Elevation.

Production. Pot. 153 B.

Wtr 363 B.

Figures Indicate Bottom of Formations.

surface clay	20
sand	111
sdv shale	264
red bed & shells	538
anhydrite	570
red bed & shale	887
shale & shell	1125
salt	1132
salt & shale	1360
shale & shells	1410
anhydrite	1430
shale & shells	1495
anhydrite & lime	1594
brkn lime	1716
lime	2015
shale	2025
shale & lime	2069
lime brkn	2128
lime	2195
shale & lime	2344
lime	2400
shale & lime	2461
shale	2606
shale & shells	2650
lime brkn	2750
lime & shale	2849
lime brkn	2908
lime	3251
lime brkn & shale	3310
lime	3390
lime & shale	3539
lime	3740
shale	3801
lime	3810
Total Depth.	

Acidized 2000 Gals. at 3810

Core Record

Core #1 3792-3810 12' rec

red & green shale 3792-3801

hrd lime, no show 3806

cherty grey lime, low

porosity, spotted sat 3810

Misener Zone 3801-3810

Potential Pumping 153 BO, 363 Wtr
(8 hr pot. 51 BO, 110 Wtr.)