

well

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas

PLOTTED

G.E. Jamison

23-24-11W

STANOLIND OIL & GAS CO.
M. Hartnett No. 1.

SEC. 23 T. 24 R. 11W.
NW NW SE
2310' N of S.L. 330' E of WL.

DEC 4 1937

County Stafford.

Total Depth. 3807
Comm. 7-30-37 Comp. 9-2-37
Shot or Treated.
Contractor.
Issued. 12-4-37

Rotary and cable.

CASING.

103/4" 245'3"
6" 3801'3"

Elevation.

Production. Pot. 974 B.

Figures Indicate Bottom of Formations.

surface formation & sand	40	shale blk	3490
rod bed and sand	90	Drilled	
rod rock	140	limo 3497-	3498
shale and red rock	225	#3 8/17 Recovery.	
rod rock	254	shale blk	3499
rod bed	510	limo and fossiliferous shale	3505
sand	528	limo grey cherty	3506
rod bed	590	Drilled	
sand	610	limo	3515
rod bed	725	limo	3696
shells and sand	820	shale	3716
anhydrite	850	#4 14/17 recovery	
shale and shells	1145	lime tan conglomerate thin strks	
shale	1285	green shale	3719
sand	1320	bright green shale	3720
shale	1365	yellow green shale	3721
sand and shale	1555	rod and green shale	3733
limo	1760	no show oil	
shale	1785	drilled	
limo	1810	shale	3735
sand	1855	#5 10/17 Recovery	
limo	1875	Green streaked shale	3752
broken limo	1900	Drilled	
limo	2150	shale	3753
broken limo	2170	# 6 17/17 Recovery.	
limo	2260	brown and green shale	3770
broken limo	2480	Drilled	
limo	2520	shale	3772
shale	2540	# 7 19/19 Recovery.	
limo	2650	brown and green shale and	
shale	2775	dolomite	3789
broken limo	2785	drilled	3791
shale	2805	# 8 17/17 Recovery	
limo	2880	shale brown	3795
sand	2905	dark green shale pyritic	3799
limo	3275	light green shale pyritic	3803
shale	3303	Misonor sand and green shale	3804
limo	3330	Misonor sand mod cryst with good	
shale	3375	sat. of oil calcareous	3808
limo	3385	Total Depth.	
shale	3405		

CORING RECORD.

8/4 Recovery
limo with few shale
partings

3450-3464

Drilled

limo

3480

2 10/17 Recovery

limo grey dense

3482

limo tan dense

3483

limo dark grey shaley

3485

limo light grey

3488

3 1/2 hours well flowed 185 bbls oil
thru 6" casing. 9-3-37

8 hours State Potential well flowed
974 bbls oil no water. thru 6" casing.

Misenen Sand 3801-3807