


STANOLIND OIL AND GAS CO.
M. Hartnett No. 4.

23-24-11W
SEC. 23 T. 24 R. 11W.
CWL SE
1320' N of S.L.
330' E of W.L.

Total Depth. 3813.
Comm. 11-13-38 Comp. 11-26-38
Shot or Treated.
Contractor.
Issued. 1-28-39

JAN 28 1939

County Stafford.



Rotary.

CASING.

103/4" 238'6
7" 3803'

Elevation.

Production. Pot. 1107 B.

Figures Indicate Bottom of Formations.

sand and shale	160
sand and clay	400
shale and lime	940
shale lime shells	1475
shale and lime	1582
broken lime	1680
sdv lime shale	1710
broken lime and shale	1755
lime	1804
broken lime	1924
broken lime & shale	1990
shale and lime shells	2055
shale	2143
broken lime	2240
shale	2340
shale and lime shells	2400
shale	2660
broken lime	2690
shale	2829
lime and shale	2929
broken lime	2976
lime	3105
broken lime and shale	3194
broken lime	3244
broken lime & shale	3316
lime	3645
shale	3690
lime	3750
shalo	3795
Core No. 1 3 1/6 Rec.	3795-3801
green shale.	
Core No. 2. 11 1/12' Rec.	3801-3813
shale green	3802
shale green sdv S.S.O	3803
sand F.X.w/good S.O.	3813
Top Misener sand	3802
Cable tools.	
Cleaned out to bottom	
Total Depth	3813.

3 hr flow test 17.20, 27.06
34.4 bbls oil no water 12-3-38

~~34.4 bbls oil no water 12-3-38~~

Misener Sand 3802-3813

Misener sand 3802-3813