

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.,

PLOTTED
J. E. Jamison

23-24-11W

STANOLIND OIL & GAS CO.
Wm. C. Volker No. 1

SEC. 23 T. 24 R. 11W.
SW NW NE
1650' N of S.L. 330' E of WL

Total Depth. 3802.
Comm. 12-6-37 Comp. 1-3-38
Shot or Treated.
Contractor.
Issued. 1-29-38

County Stafford.



CASING. Rotary 3795
Cable 3802

JAN 29 1938

103/4" 250'
6" 3789'

Elevation.

Production. Pot. 1709 B.

Figures Indicate Bottom of Formations.

sand clay gravel & shalo	300
sand and red clay	510
shale and lime shells	1410
shale sdy lime & lime	1560
broken lime and shalo	1635
shale and lime	1717
lime	1750
shale	1772
broken shale and lime	1887
broken lime	2002
shale and lime	2077
broken lime and shale	2282
shale	2372
broken lime and shale	2532
shale and lime	2620
broken lime and shale	2685
broken lime	2738
shale	2806
shale and lime	2867
shale	2900
broken lime	2951
lime	3095
shale and lime	3142
broken lime	3198
lime	3236
shale and lime	3314
shale	3372
lime	3472
Top of Lansinglime	3400
broken lime	3467
lime	3600
broken lime	3690
shale	3726
broken lime	3772
shale	3790

top of sand 3791
cable tool Record.
made when plug was drilled 3795-3797
sand 3802
Total Depth.

started flowing 3797- 3798
flowed 19.7 bbls in 15 min. 3798
flowed 21.3 bbls in 15 min 3799
flowed 23.6 bbls in 15 min
and contined this for
1 1/2 hours 3799- 3802
M. S. M.
Simpson sand 3791- 3802
flowed at 3798 19.7 bbls oil in 15 min.
thro 6" casing.

Coring Record Rotary
core No. 1 3790- 5' 4 1/2 Rec.
sand pyrotic shale 3791
sand mod Cryst. 3795