


STANOLIND OIL & GAS CO.
Wm C. Volker No. 2.

23-24-11W copy made
SEC. 23 T. 24 R. 11W
NW 1/4 NE
2310' N SL 330' E WL

County. Stafford



Elevation.

Production. Pot. 2243 B.
No wtr.

Figures Indicate Bottom of Formations.

surface sand	70
red bed	500
sand & shale	650
shale & shells	1410
brkn lime	1570
brkn shale & lime	1680
brkn lime	1830
brkn lime & shale	2040
shale & sand	2140
shale & lime shells	2215
shale & lime	2315
shale & lime shells	2495
shale	2590
shale & lime shells	2680
shale	2860
shale & lime	3025
brkn lime	3095
brkn lime & shale	3160
brkn lime	3285
lime & shale	3390
lime	3495
brkn lime	3540

Top Lansing 3405

lime	3575
brkn lime	3665
lime	3805

Top Unconformity 3804

Core #1 9' rec.	
sand grey, coarse crys. sat	
Core #2 9' rec 3815-3825	
sand coarse crys sat	3821
sdv lime stone, fine	3822
sand crystals, sat	
sand coarse crys sat	3825
Core #3 5' rec	3830
sand coarse to fine crys	
lime strks, sat	3827
cherty lime porous sat	3828
lime, green clay, dense no sat	3830
Total Depth.	

Top Lansing 3405
Misener zone 3804-3830
Flowed 105 bbls per hr on 2 hr test.