

24-24-1148.8.8.
Card made out

SINCLAIR PRAIRIE OIL CO.
Elizabeth A. McComb No. 1.

SEC. 24 T. 24 R. 11W
NW 1/4 SW
330' fr N & WL W 1/2 SW 1/4

County. Stafford

Total Depth. 3812'


Comm. 4-26-38 Comp. 5-24-38

Shot or Treated.

Contractor. Harbar Drlg. Co.

Issued. 10-1-38 Rotary 3800
Cable 3812

OCT 1 1938



CASING:

13" 215'

7" 3792'

3" tbg 3798'

Elevation.

Production. Pot. 804 B.

Figures Indicate Bottom of Formations.

clay & sand	69
sand & shale	224
shale & shells	920
salt	1235
salt & shalo	1380
lime	1388
shale	1420
shale & lime	1505
lime	1690
anhydrito	1715
lime	1810
shale hrd	1820
lime & shalo	1905
lime	2110
hrd shale & shells	2130
shale & lime	2270
lime brkn	2355
lime	2375
shale & lime	2585
lime	2610
shale	2645
lime & shale	2700
lime	2740
shale & shells	2830
lime	2850
shale	2905
lime gas show 3090-3100	3258
lime & sand	3290
lime	3305
shale & lime	3360
shalo Top KC 3408	3400
lime	3690
shale	3701
lime	3730
Base of KC 3730 (No oil show)	
shalo & lime	3788
Top Misener lime 3788	
sand Misener Top 3794	3812
Total Depth,	

Potential 804 bbl oil after
2-5 Qt shots in Misener sand