

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

27-24-11W

STANOLIND OIL & GAS CO.
Ray McComb No. 1.

SEC. 27 T. 24 R. 11W
NEc NE
2310' N SL 2310' E WL

Total Depth. 4060'
Comm. 3-3-38 Comp. 4-21-38
Shot or Treated.
Contractor.

County. Stafford

Issued. 6-4-38 Rotary O-3857
Cable 3857-79



CASING:
13" 254'6"
7" 3340'10"

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & gravel	160	Core #3 3/3 Recovery	
red bed & shale	256	Ls coarse cryst.(fossiliferous)	
red bed	533	no show	3864
anhydrite	560	Core #4 1/1 recovery	
red bed	710	sdv lime	3865
shale, red & blue	827	Core #5 3/3 recovery	
shale & shells	1120	lime	3868
salt & shale	1360	Core #6 3/3 recovery	
shale & shells	1535	sdv lime	3871
lime brkn	2616	Core #7 3/3 recovery	
brkn lime & shale	2692	sdv lime	3874
brkn lime	2753	drilled lime chert	3879
brkn lime & shale	2860	hole filled 1500' wtr 2 Hrs.	
brkn lime	2971	Rotary Tools	
lime	3290	lime	3880
lime, shale, sand	3350	chert & sand	3886
shale sticky	3405	lime hrd & chert	3905
shale	3416	lime & chert hrd	3917
Top Lansing 3416		lime	3928
lime	3720	lime, sand	3936
shale & shells	3742	lime hrd & chert strks	3941
chat	3753	sdv lime hrd	3944
shale	3818	lime hrd	3956
Top Marmaton 3720		Simpson sand	3960
Top Mississippian 3735		Core #1 9" 2/12 1/2 recovery	
Top Cherty Cong. 3735		lime wht to gray ex no show	3972 1/2
Top Kinderhook 3772		Drilled	
Core #1 3/5 recovery		lime hrd	3975
chert dull gray	3819	Top Simpson 3975	
shale red & green	3825	Simpson	3977
Core #2 12/12 recovery		Core #2 9 1/2/15 recovery	
shale green	3834	shaley green with ls	
shale green sdv pyritic	3835	inclusions	3983
Core #3 4/6 recovery		shale green	3990
shale green pyritic	3837	sand fine, no show	3992
sand very tight(SSO 38 1/2-39)	3839	Core #3 10/11 recovery	
lime tan ex to mx	3841	sand fine with phosphate inclusions.	
Top Sand		no show	4003
Core #4 4/6 recovery		shale	4036
L.S. gray to wht, mx w/ SSO	3853	shale & lime	4045
L.S. Cx sdv w/ SO	3854	Top Siliceous 4044	
chert wht dense	3855	Core #4 6/11 recovery	
sand c.x. w/ S.O.	3856	dolomite porous	4048
L. S. ex with F.S.O.	3857	dolomite dense, no show oil	4056
Top Viola 3856		Coros sh lime porous strong	
Core #5 2/2 recovery		sulphur wtr small	4056
Ls gray w/ SO	3859	brkn lime	4060
Derrick Floor Corr. 3859-3857		Total Depth.	
Cable Tools			
Core #1 1/2 recovery			
limestone coa rse cryst. wht			
very slight SO dense	3859		
Core #2 No record			
Ls wht, coarse cryst. sdv			
sft probably carries wtr	3860		
Ls wht, coarse crystals no			
show	3861		

Misener sand top 3835
Viola lime top 3854
Simpson sand top 3975
Siliceous lime 4044-4060