

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 185 — 20,558
County Number

Operator

Delta Western Co. & G. Reed

Address

Suite 645, Fourth Financial Center Wichita, Kansas 67202

Well No.

#1

Lease Name

Irvine

Footage Location

990

feet from (N) ☒ line

1650

feet from (E) ☒ line

Principal Contractor

Red Tiger Drilling

Geologist

George A. Reed

Spud Date

January 1, 1975

Total Depth

3924'

P.B.T.D.

Date Completed

January 9, 1975


Oil Purchaser

None

S. 30 T. 24 R. 11 E W

Loc. SE NW NE

County Stafford

640 Acres
N

Locate well correctly

Elev.: Gr. 1838

DF 1840 KB 1843

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{2}$	8-5/8	20 $\frac{1}{2}$	302'	Common	250	290 gel. 390 CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DELTA WESTERN CO. & G. REED		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: DRY HOLE	
Well No. #1	Lease Name Irvine		
S30 T24 R11 ^{EX} _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			ELECTRIC LOG
			ANHYDRITE 614 (_1229)
			HEEBNER SH. 3296 (-1453)
			BROWN LIME 3452 (-1609)
			LANSING 3481 (-1638)
			B/KANSASCITY 3762 (-1919)
			KINDERHOOK 3813 (-1970)
			VIOLA 3913 (-2070)
			TD 3924 (-2081)
DST #1 3913-3918 Open 10, shut in 20, open 45, shut in 45 Strong blow throughout, Recovered 80' fluid (70' slightly oil and gas cut mud, 10' filtrate water) with 2100' gas on top of fluid. Free oil noted in tool IBHP 338#; FBHP 338#; IFP 23-29#; FFP 34-41#			
DST #2 3913-3924 Open 10 min., shut in 20, open 2 hours, shut in 45 minutes. Strong blow throughout. Gas to surface in 17 minutes after 2nd opening. Recovered 510' fluid (30' heavily oil cut thin mud, 120' froggy oil, slightly water cut, 60' heavily oil cut water, 60' slightly oil cut water and 240' water. IBHP 322#; FBHP 302#; IFP 21-42#; FFP 73-218#			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
<div style="border: 1px solid black; border-radius: 50%; width: 150px; height: 150px; display: flex; align-items: center; justify-content: center; margin: 0 auto;"> </div>		<div style="text-align: center;"> <div style="display: flex; justify-content: center; align-items: center;"> <div style="border-bottom: 1px solid black; width: 150px; margin-right: 5px;"></div> <div style="font-size: small;">Signature</div> </div> <div style="display: flex; justify-content: center; align-items: center;"> <div style="border-bottom: 1px solid black; width: 150px; margin-right: 5px;"></div> <div>George A. Reed, Operator</div> </div> <div style="display: flex; justify-content: center; align-items: center;"> <div style="border-bottom: 1px solid black; width: 150px; margin-right: 5px;"></div> <div style="font-size: small;">Title</div> </div> <div style="display: flex; justify-content: center; align-items: center;"> <div style="border-bottom: 1px solid black; width: 150px; margin-right: 5px;"></div> <div>January 17, 1975</div> </div> <div style="display: flex; justify-content: center; align-items: center;"> <div style="border-bottom: 1px solid black; width: 150px; margin-right: 5px;"></div> <div style="font-size: small;">Date</div> </div> </div>	