

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


30-24-11W

Company- COOPERATIVE REFINERY ASSN \* REX & MORRIS  
Farm- McMillan "A" No. 2 DRLG CO.

SEC. 30 T. 24 R. 11W  
NE SE NW

Total Depth. 3911  
Comm. 10-20-54 Comp. 11-14-54  
Shot or Treated.  
Contractor. Rig #5 Company  
Issued. 4-2-55

County Stafford  
KANSAS



CASING:

8 5/8" 315' cem w/200 sx  
5 1/2" 3920' cem w/100 sx

Elevation. 1839 DF

Production. 137 bbls oil

Figures indicate Bottom of Formations.

surface hole 315  
shale,sand,shale 950  
shale, shells 1430  
shale, lime 1610  
shale,salt,shells 1750  
shale, lime 3480  
lime 3605  
lime, shale 3635  
lime 3665  
lime, shale 3715  
lime 3850  
lime, shale 3900  
lime 3911  
Total Depth

Tops:  
Heebner 3290  
Toronto 3301  
Douglas 3326  
Brown Lime 3442  
Lansing 3472  
Base Kansas City 3752  
Kinderhook 3802  
Viola 3899

RTD 3907

Producing formation-Viola

All Measurements are from D.F.

Lansing 3722-3424 (2') Fair show of free  
oil in mottled gry  
lithographic limest.  
spotted pinpoint poro.  
no visible permeability.

Viola 3899-3907 (8') Tight, wht to lgt  
gry, med. xyn cherty  
dolo. Trace of free  
oil & gas bubbles. Good  
odor.

DST 3901-07 Open 1 hr. Strong blow  
Throughout. Shut in 20 mins. Rec. 3000'  
gas & 120' heavily gas cut oil. BHP 700#  
No flow pressures.