

30-24-11W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATIONAL COOPERATIVE REFINERY ASSOC.
Farm- Minks No. 1

SEC. 30 T. 24 R. 11W
NE NW SE

Total Depth. 3905
Comm. 2-28-55 Comp. 3-12-55
Shot or Treated.
Contractor. Anschutz Drlg. Co., Inc.
Issued. 5-14-55

County Stafford
KANSAS



CASING:
8 5/8" 314.64' cem. w/200 sx
5 1/2" 3901' cem. w/75 sx

Elevation. 1837 RR

Production. 91 bbls. oil

Figures indicate Bottom of Formations.

surf. clay & sand	120
sand	145
shale, shells & redbed	318
redbed & shale	608
Anhydrite	623
shale & shells	675
shale, shells & salt	1575
lime & shale	1805
lime	1905
lime & shale	2770
shale & shells	2845
lime & shale	3095
lime	3295
lime & shale	3534
lime	3638
lime, chert & shale	3690
lime & shale	3902 RTD
shale & lime	3905
Total depth	

Scout Tops:	
Anhydrite	608
Heebner	3297
Brown lime	3441
Lansing	3472
Viola	3900