

51643

STANOLIND OIL & GAS CO.
E.H. McComb No. 2.

SEC. 12 T. 24 R. 11W
CSL SW SW
330°N SL 660°E WL

Total Depth. 3761'

Comm. 6-6-39


Comp. 6-27-39

Shot or Treated.

Contractor.

Issued. 8-5-39

County, Stafford



CASING:

10 $\frac{3}{4}$ "

6 "

248'6"

3741'

Rotary

3751

Cable

3761

Elevation.

Production. Pot. 446 B.

Figures Indicate Bottom of Formations.

sand, gravel & clay	170
red bed	490
anhydrite	520
shale	1040
salt & shale	1250
shale & shells	1593
brkn lime & shale	1723
brkn lime	1810
lime	1835
shale & lime	1916
shale & shells	2010
lime brkn	2112
lime & shale	2222
lime brkn	2388
lime & shale	2650
lime brkn	2716
lime	2783
shale & shells	2890
lime brkn	3119
lime	3169
lime brkn	3285
shale	3380
lime	3544
lime brkn	3627
lime	3653
lime brkn	3705
shale	3739
sand shaley	3741
sand	3760
lime Viola	3761
Total Depth.	

Misener sand 3739-3760

Flow test thru casing - 98 B. 1st
hr, 69 B. 2nd hr

Potential 446 Bbls (Prod. last 4
hrs 50.16 B., no wtr)