

51960

STANOLIND OIL & GAS CO.
E. McComb No. 4.


SEC. 12 T. 24 R. 11W
CNL NW SW
2310' N SL 660' E WL SW $\frac{1}{4}$

DEEPENING RECORD

County. Stafford

Total Depth. 3785'
Comm. 9-22-39 Comp. 10-13-39
Shot or Treated. 2000 Gals.
Contractor.
Issued. 1-4-41

Rotary 3736
Cable 3754



CASING:

8 5/8" 240'
5 1/2" 3729' 13/4"

Elevation.

Production. Pot. 359 B.
No wtr

Figures Indicate Bottom of Formations.

cellar	9
surface clay & red bed	285
red bed & shale	495
anhydrite	520
shale	715
shale & sand	1055
shale & lime	1485
lime	1652
lime brkn	1918
lime	1950
brkn lime & shale	2005
lime brkn	2035
shale	2120
brkn lime & shale	2211
shale	2615
shale & lime	2747
shale	2895
lime	3225
shale	3296
brkn lime & shale	3358
lime	3642
shale	3730
sand	3748
limestone	3749
sdv limestone	3752
sand	3753
lime Viola	3754
Total Depth.	

DEEPENING RECORD

Comm. 11-1-40
Comp. 11-4-40
Production - Pot. 3418 B.

lime 3754-66
lime cherty 3771
dolomite 3772
limoy dolomite cherty 3775
dolomite cherty 3778
limoy dolomite cherty 3783
lime 3785
Total Depth.

Misener formation 3730-53

10-15-39 Acidized 2000 Gals.