

STANOLIND OIL & GAS CO.
O. J. Hartnett No. 7.

SEC. 13 T. 24 R. 11W
CWL E/2 NW
1320' N SL 1650' E WL

DEEPENING RECORD

Total Depth. 3817'

Comm. 1-23-39 Comp. 2-12-39

Shot or Treated.

Contractor.

Issued. 12-13-41 Rotary 3771
Cable 3817

County. Stafford



CASING:

10 3/4"

7"

253'

3765' 1"

Elevation.

Production. Pot. 1449 B.
No water

Figures Indicate Bottom of Formations.

shale blue	62	Core Record	
sand	170	Core #1 3758-3771 13' rec	
shale red	253	shale green	3765
red shale & shells	505	sand med, w/very good	
anhydrite	525	sh oil	3771
shale	578	Core #2 3771-3777 5' rec	
shale & shells	842	sand shaly fine cryst	
shale, anhydrite, lime	866	hrd sh gas & oil	3777
shale & shells	1030	Core #3 3777-3783 4' rec	
salt, shale, shells	1365	sand hrd shaly SSO	3780
shale & shells	1440	sand fine to coarse	
anhydrite	1557	cryst sft sat	3783
anhydrite & lime	1694	Core #4 3783-3786 1' rec	
shale & lime	1727	sand med sft porous,	
lime brkn	1739	well sat, slightly	
sdv lime	1762	cherty at base	3786
lime brkn	1783	Core #5 3786-3789 2' rec	
lime	1848	sand med fine, good	
lime & shale	1912	sh oil	3788
sdv shale	1943	sand very coarse	
lime	2082	cherty very light	
lime & shale	2123	sh oil	3789
lime brkn	2142		
lime & shale	2167		
lime	2230	<u>DEEPENING RECORD</u>	
sdv shale	2265		
lime & shale	2407	Comm. 8-9-41 Comp. 8-13-41	
lime	2431	Prod-BHPB Pot. 22,100 BO,	
lime & shale	2530	no wtr	
lime	2648		
lime & shale	2870	dolomite	3789-95
shale	2920	lime	3802
lime & shale	2951	lime & shale	3803
lime	3096	lime & chert	3817
lime & shale	3170	Total Depth.	
lime	3242		
shale & shells	3295		
shale	3319	Viola lime 3789-3817	
lime & shale	3341		
lime	3354	Acidized-flowing test	
lime & shale	3364	thru 1" choke averaged	
shale	3384	72 BOPH, no wtr for 2 hrs	
lime & shale	3414	Btm Hole pressure bomb	
lime	3513	Pot. 22,100 BO, no wtr-	
lime & shale	3575	Flowed 147 BO in 4 hrs	
lime	3641		
lime & shale	3694		
lime	3711		
lime & shale	3745		
shale	3765		
sand	3789		
Total Depth.			

Misener sand 3765-3789

3 hr test thru casing 1st

hr. 68, 2nd hr 60, 3rd hr

63 BO, no wtr