

WELL DATA SHEET

Lease ZU Well No. 15 Pool Zenith Date 5/90

Location NW/4 Sec. 23-24S-11W County Stafford State Kansas

Dist. "H"  
4 ' From  
KB to GL

Date Completed 3-31-84  
 Well Elevation 1803 GL, 1807 KB  
 Producing Formation \_\_\_\_\_  
 From \_\_\_\_\_ ' To \_\_\_\_\_ ' From \_\_\_\_\_ ' To \_\_\_\_\_ '  
 From \_\_\_\_\_ ' To \_\_\_\_\_ ' From \_\_\_\_\_ ' To \_\_\_\_\_ '

Initial Production \_\_\_\_\_ bopd \_\_\_\_\_ bwpd \_\_\_\_\_  
 \_\_\_\_\_ mcf/d \_\_\_\_\_ GOR \_\_\_\_\_

Initial Treatment  
3-3-84 Drill out cmt to 3892, perf Viola 3845-60, acd 1500 gal, ON FL 1600', swab 100% wtr, set CIBP @ 3835  
3-7-84 Perf 3804-12, acd 400 gal, ON FL 1750, swab 30+ BPH 30% oil, put on pump  
4-4-84 Pump test 118 BO, 300 BW

Subsequent Workover or Reconditioning:  
6-11-84 Pull well, perf 3815-19, no trtmt or swab, re-ran pmprg equip, no test info

Top of Cement  
 @ \_\_\_\_\_

Present Production \_\_\_\_\_ bopd \_\_\_\_\_ bwpd \_\_\_\_\_  
 \_\_\_\_\_ Gas \_\_\_\_\_ mcf/d \_\_\_\_\_  
 From \_\_\_\_\_ ' To \_\_\_\_\_ '  
 Static F. L. @ \_\_\_\_\_ ' Date \_\_\_\_\_  
 Pumping F. L. @ \_\_\_\_\_ ' Date \_\_\_\_\_

3804  
 3812 L. Mishner Sd  
 3815  
 3819

CIBP @ 3835

3845  
 3860 Viola 1

Remarks: Did not get primary cmt displaced f/csg found cmt @ 3717 when going in to run bond log

5/2 "OD # \_\_\_\_\_ Thd \_\_\_\_\_  
 Gr. \_\_\_\_\_ Casing  
 Set @ 3899 w/ 175 sx

TD 3900