

WELL DATA SHEET

Lease Stewart Well No. 2-5 Pool Zenith Date 5/90  
Location 1/2 Sec. 12-245-11W County Stafford State Kansas

Dist. "H"  
4 ' From  
KB to GL

Date Completed \_\_\_\_\_  
Well Elevation 1804 GL ; 1808 KB  
Producing Formation \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

Initial Production \_\_\_\_\_ bopd \_\_\_\_\_ bwpd \_\_\_\_\_  
\_\_\_\_\_ mcf/d \_\_\_\_\_ GOR \_\_\_\_\_

Initial Treatment  
2-22-85 Perf 3720-30, acidz 1000 gal, ON FL  
2000' 100% wtr, sgz w/100 sx, drill out

2-28-85 Perf 3768-73, no trtmnt, 100% wtr, ON  
FL 1600', set CIBP 3755

3-1-85 Perf 3720-23, acidz 350 gal, swab 100%  
wtr, ran tracer survey, indicated commun. to lower perms  
Subsequent Workover or Reconditioning:

3-6-85 Sgz perms 3720-23 w/200 sx, drill out

3-8-85 Perf 3720-22 1/2, acidz, swab 100% wtr,  
sgz w/100 sx, drill out

3-15-85 Perf 3720-24, stress trac, acidz 500 gal,  
ON FL 2000', 70% oil, put on prmp

3-20-85 Pmp tst 71.5 BPD 98% oil

Top of Cement  
@ \_\_\_\_\_

3720  
3724 L. Misner Sd

Present Production \_\_\_\_\_ bopd \_\_\_\_\_ bwpd \_\_\_\_\_  
\_\_\_\_\_ Gas \_\_\_\_\_ mcf/d \_\_\_\_\_  
From \_\_\_\_\_ To \_\_\_\_\_  
Static F. L. @ \_\_\_\_\_ Date \_\_\_\_\_  
Pumping F. L. @ \_\_\_\_\_ Date \_\_\_\_\_

CIBP @ 3755

3768  
3773 Viola 1

Remarks: \_\_\_\_\_

5 1/2 "OD # \_\_\_\_\_ Thd \_\_\_\_\_  
Gr. \_\_\_\_\_ Casing \_\_\_\_\_  
Set @ 3849 w/ 175 sx

TD 3850