

WELL DATA SHEET

Lease ZU Well No. 35 Pool Zenith Date 5/90
 Location S/2 Sec. 1-24S-11W County Stafford State Kansas

Dist. "H"
5 'From
KB to GL

Date Completed

Well Elevation 1798 GL, 1803 KB

Producing Formation

From _____ To _____ From _____ To _____
 From _____ To _____ From _____ To _____

Initial Production

bopd

bwpd

mcf/d

GOR

Initial Treatment

8 5/8 "OD Surface
 Pipe set @ 212 '
 w/ 150 SX.

1-23-86 Perf 3740-43, 3735-38, acidz 350 gal,
swab dn 17% oil, re-acidz 1000 gal, ON FL
3200', swab 2-5 BPH 6-8% oil

1-29-86 Perf 3703-07, isolate w/RBP, stress frac,
acidz 500 gal, ON FL 3200', swab 4 BPH 2-3% oil,
re-acidz 1500 gal, swab 8 BPH 6-11% oil, pull RBP,
put on pmp, test 43 BPD 20% oil 2-14-86

Subsequent Workover or Reconditioning:

Top of Cement

@ 2800

4-16-86 Ran RBP & pkr, isolate Viola perms, frac
w/4000 # sd, set BP between Viola & Misner,
frac Misner 6000 # sd, attempt to pull RBP,
plug stuck 3628, mill on RBP, push RBP to
bottom 4-25-86, put on pmp

5-8-86 Pmp test 267 BPD, 6% oil

Present Production

bopd

bwpd

Gas

mcf/d

From

To

Static F. L. @

Date

Pumping F. L. @

Date

3703 L. Misner sd
3707

3735 Viola 1
3738

3740 Viola 1
3743

Remarks: Junk in bottom of hole

5 1/2 "OD # _____ Thd _____
 Gr. _____ Casing _____
 Set @ 3817 w/ 175 SX

TD 3818