

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union Nat'l Bk Bldg, Wichita, Kansas.

Plotted - 90°B.
15-24-12W

STANOLIND OIL AND GAS CO.
R. Charles No. 1

SEC. 15 T. 24 R. 12W.
CN¹/₂ NE SE
2310' N. SL 1980' E. WL. SE¹/₄

DISCOVERY WELL

Total Depth. 4021.
Comm. 6-24-40 Comp. 7-18-40
Shot or Treated.
Contractor.
Issued. 9-28-40

County Stafford.

CASING.

Rotary
Cable

85/8" 244'4"
5 1/2" 3994'6"

Elevation.

Production. Pot. 11,324 B.

Figures Indicate Bottom of Formations. Draw down.

cellar	7'3"
surface dirt	30
sand	60
shale sand shells	165
shale shells	230
red rock	250
red rock and shale	649
anhydrite	685
shale and shells	1195
salt and shale	1400
shale and shells	1500
shale	1545
anhydrite	1645
shale	1655
lime	1705
brkn lime	1836
lime	1904
broken lime	1970
sdv	2000
lime	2018
broken lime	2170
shale	2260
lime	2326
broken lime	2411
shale	2505
shale sdv	2530
broken lime	2560
sdv lime	2620
broken lime	2711
broken lime & shale	2786
lime	2862
broken lime & shale	2995
lime	3035
lime broken	3090
lime	3125
broken lime	3156
lime	3193
broken	3325
shale	3360
shale lime shells	3475
lime	3503
lime hard	3518
lime	3701

shale and lime	3739
lime	3774
shale	3802
lime	3804
shale	3815
lime	3825
chert and lime	3840
chert and dolomite	3906
lime	3938
lime sand and shale	3963
shale and sand	3985
shale	3994
lime	3996
dolomite	4021

Total Depth.

Tops.

Anhydrite	649
Topeka	3010
Lansing	3470
Viola	3815
Simpson	3935
Arbuckle	3994-4021

Swabbed 7 bbls of oil no water per
hour off bottom before acid. 7-31-40

