

15-24-12W *Ph*

50

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL & GAS CO.
R. Charles "B" No. 4

SEC. 15 T. 24 R. 12W.
CN $\frac{1}{2}$ SW SE
990' N of SL 660' E of WL SE $\frac{1}{4}$

Total Depth. 3964
Comm. 3-1-41 Comp. 5-7-41
Shot or Treated.
Contractor.

County Stafford.

Issued. 7-12-41 Rotary O-3955
Cable 3955-64

CASING.

35/8"
5 $\frac{1}{2}$ "

253'4" cemented.
3946' cemented.

Elevation.

Production. Pot. 1098 B.

Figures Indicate Bottom of Formations. 92 B.W. drawdown

cellar	6
surface sand	192
red bed and shale	265
red bed and sand	465
red rock	656
anhydrite	690
shale	845
shale and shells	1217
shale	1550
shale and lime shells	1700
broken lime	1798
lime	1874
broken lime	1935
shy shale	1960
lime	2095
shale	2121
broken lime	2269
lime	2300
shale	2350
lime	2360
shale	2485
shale and shells	2680
shale	2715
lime	2832
broken lime & shale	2932
shale and shells	2960
lime	3230
broken lime	3272
lime	3312
shale and shells	3392
shale	3468
lime	3537
broken lime	3544
lime	3578
broken lime	3609
lime	3746
lime and chert	3799
shale and chert	3820
lime and chert	3820
shale lime and chert	3886
lime	3898
shale	3944
dolomite	3964
Total Depth.	

Tops: Anhydrite 656
Viola 3775
Simpson 3883
Arbuckle 3945-3964

Swabbed 20 bbls oil, no water per hr for 3 hours thru 2 $\frac{1}{2}$ tubing
Swabbing from 1000' off bottom.