

15-24-12W *lotted*

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL AND GAS CO.
C.B. Crawford No. 3

SEC. 15 T. 24 R. 12W.
CN $\frac{1}{2}$ SE NE
990' N of SL. 1980' E of WL
NE $\frac{1}{4}$

Total Depth. 3832
Comm. 4-2-41 Comp. 4-20-41
Shot or Treated.
Contractor.
Issued. 7-5-41

County Stafford.

Rotary.

CASING.

65/8" 258'5" cemented.
5 $\frac{1}{2}$ " 3822'4" cemented.

Elevation.

Production. Pot. 22,239B
No wtr

Figures Indicate Bottom of Formations.

collar	6'2"
surface sand	150
red bed	630
shale	650
anhydrite	675
shale and red bed	1414
shale and limo	1504
shale	1600
shale and limo	1650
broken limo	1670
shale	1715
limo and shale	1910
broken limo	1970
shale	2000
limo	2005
shale and lime	2098
broken limo	2186
broken lime and shale	2261
shale and limo	2379
shale and sholls	2478
limo and shale	2550
broken lime	2598
shale	2740
shale and limo	2880
shale	2987
limo	3057
broken limo	3110
lime hard	3153
limo	3390
shale	3448
shale and lime	3530
limo	3716
shale and limo	3735
shale	3772
lime	3801
shale	3819
dolomite cherty	3832
Total Depth.	

Top Anhydrite 650
Viola 3819-3832

Flowed 173 bbls oil, no water, thru casing in 8 hours
after drilling plug and C.O. to bottom.
Initial 3-4 rate BHPB Pot. 22,239 bbls oil, no water