

STANOLIND OIL & GAS CO.
C. Crawford No. 7

SEC. 16 T. 24 R. 12 W.
CWL NW NE
1980' N SL 330' E WL NE $\frac{1}{4}$

Total Depth. 3848
Comm. 12-2-41 Comp. 12-21-41
Shot or Treated.
Contractor.
Issued. 3-21-42

County Stafford.



Rotary
CASING

85/8" 239' cemented.
5 1/2" 3835' cemented.

Elevation.

Production. Pot. 4830 B.
Drawdown. no wtr

Figures Indicate Bottom of Formations.

cellar	5'4
surface clay & sand	164
shells	223
red bed and shale	254
red bed	650
anhydrite	670
red bed and shale	938
salt and shale	1545
shale	1575
lime and shale	1645
lime	1852
lime and shale	1909
broken lime & sand	2027
lime	2080
lime hard	2110
shale and shells	2134
lime and shale	2225
sand	2240
lime	2295
broken lime	2320
lime soft	2390
lime	2407
lime and shale	2473
shale	2640
shale and lime	2722
lime	2795
lime and shale	2852
shale	2906
broken lime	2968
lime	2993
shale and lime	3043
broken lime	3097
lime	3125
lime soft	3138
lime and shale	3340
shale	3412
lime	3440
shale	3510
lime oil odor	3549
lime	3717
shale	3759
lime	3805
shale	3826
lime	3833
shale	3838
lime	3848

Total Depth.

Viola lime 3838-3848