

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

3-24-12W

Company - HUBER ETAL
Farm - Bartlett

No. 1

SEC. 3 T. 24 R. 12W
NE NE SW

Total Depth. 4048

Comm. 12-1-48

Comp. 1-20-49


County. Stafford

KANSAS

Shot or Treated. Acid

Contractor. Crown Oil Co.

Issued. 4-2-49



CASING:

8 5/8" 170' cem w/175 sx.
5 1/2" 3910' cem w/100 sx.

Elevation. 1865 *ft.*

Production. Dry

Figures Indicate Bottom of Formations.

cellar	4	Drilled cement to 3882, perf. 24/3830-38
clay	20	set 1 1/2 hrs. no fluid. Perf. 23/3837-45
sand	50	very small show oil on gun ports 3844-45,
sand, clay	70	shut down 1 hrs, no fluid, perf 24/3844-52,
clay	90	Washed hole w/150 gals water w/casing swa b,
sand	150	bailed dry, no shows. Dumped 1 bbl water on
shale, shells	169	bottom then 1/2 bbl acid. Let set 2 1/2 hrs,
redbed	295	bailed dry and had rainbow in water, no free
shale red	655	oil. Perf. 24/3851-59, wait 1 hrs, no fluid.
lime	680	Dumped 125 gals acid on bottom and loaded
shale	775	hole w/1200' water, set 1 1/2 hrs, swbd. down
shale, shells	1470	and had no shows. 500 acid thru casing, swbd
shale, limeshells	1610	down and swbd 28 1/2 bbls water plus 4 BO/3 hrs.
lime, shale	1680	Filled up 1000' fluid in hole/2 1/2 hrs. Swbd
lime, shale brkn	1750	39.9 bbls wtr plus 1.6 bbl oil/3 hrs. Shut
lime	2155	down 8 hrs. Swbd 45.9 bbls water plus 1.16
lime, shale brkn	2265	bbl oil/3 hrs. Dry and aband.
lime, shale	2880	
lime brkn	3045	
lime, shale	3085	
lime	3125	
lime, shale brkn	3228	
lime	3290	
shale, lime	3156	
lime	3745	
lime, shale	3771	
shale	3807	
shale, lime	3836	
lime, chert	3864	
lime	3887	
lime, chert	3940	
lime, shale	3965	
shale	3994	
lime	4048	
Total depth		

Tops:

Lansing	3445
Viola	3830
Simpson	3948
Arbuckle	3998

3830-51, chert and coarse xlyn
limestone in part dolomitized,
poor spotted prosity and trace
staining.

3851-63, dolomite and chert, med.
fine xlyn, fair porosi'y in part,
fair stain, no odor.

DST 3834-64, open 1/2 hr, rec. 180'
gassy mud w/few spots free oil.
BHP 175#, in 10 mins.

3865-71, dolomite med fine xlyn
fair to good porosity in part
stained, no odor.

Rotary total depth 4048, no shows.
Schlumberger.