

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

4-24-12W

Company- CITIES SERVICE OIL CO.
Farm- Kelly "B" No. 1

SEC. 4 T. 24 R. 12W
SE NW SW
990' S. & 990' E. of W/4 corner

Total Depth. 3945

Comm. 3-8-52


Comp. 3-19-52

Shot or Treated.

Contractor. R. W. Rine Drlg. Co.

Issued. 7-12-52

County Stafford
KANSAS



CASING:

8 5/8" 313' com. w/250 sx

5 1/2" 3941' com. w/150 sx

Elevation. 1879

Production. 6,200,000 Gas

Figures Indicate Bottom of Formations. B. P. Ind. Capacity

clay, sand, shale & shells	316
shale & shells	1770
lime & shale	2085
lime	2200
lime & shale	2900
lime	3330
shale & lime	3470
lime	3770
lime & chert	3799
lime	3841
lime & chert	3860
cherty lime	3910
lime & chert	3920
lime	3945

3945 RTD = 3941 SLM

Total Depth

Tops: Corr.

Brown Limestone 3431

Lansing 3456

Viola 3793

Simpson 3926

Penetration 15'

Drilled cement to 3925' SLM

Perf. 48 shots 3820-30'

3-27-52 Az. 500 gals. 3820-30'

2,900 H.D.F. gas through 2" tubing;

S.I.P. 950#.

Killed well and set Baker plug at
3815 SLM.

Perf. 56 shots 3795-3809'.

3-29-52 Az. 1000 gals. 3795-3809'

Drilled bridge plug to 3925'

4-4-52 5,020 H.C.F. gas through

2"; S.I.P. 965#.