

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

8-24-12W


Company - EL DORADO REFG.
Farm - O'Connor No. 1

SEC. 8 T. 24 R. 12W
NE NE SE

Total Depth. 3914
Comm. 6-25-51 Comp. 7-30-51
Shot or Treated.
Contractor. Sterling Drlg.
Issued. 8-25-51

County. Stafford

KANSAS



CASING:

8 5/8" 264' cem. w/150 sx.
5 1/2" 3917' cem. w/50 sx.

Elevation. 1886 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

sand	80
shale & shells	264
red bed	675
anhyd.	705
shale	825
shale & shells	1375
shale & lime	1765
lime	2350
lime & shale	3010
lime	3325
shale & lime	3425
shale	3495
lime	3850
shale	3853
Viola lime	3914
Total Depth	

Tops: D.F.	
Hoebner	3313
Brown lime	3413
Lansing	3493
Congl.	3803
Viola	3850

Perf. from 3839-3893 w/16 holes.
Perf. 3878-3882 w/16 holes.
Squeezing perf. from 3878-3882
Squeezed yesterday w/250 sx,
packer set at 3850 standing
press. 2500"
Perf. w/70 shots from 3857-3867
Az. w/100 gals.

D.S.T. 3851-67, op. 45 min. gas to
surf. in 25 min. est. 200,000 plus
or minus, rec. 100' heavy gas cut mud
and some free oil BHP 1250".