


CITIES SERVICE OIL CO.
 Byer No. 2.

SEC.10 T.24 R.12 W
 CSL SW SE
 330' N 660' E of S $\frac{1}{2}$ Cor.

Total Depth. 3871'
 Comm. 7-14-42 Comp. 8-2-42
 Shot or Treated. None
 Contractor. Earl F. Wakefield
 Issued. 10-10-42

County. Stafford



CASING:
 8 5/8" 398' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	35
sand	150
shale red	398
red bed	665
anhydrite	677
shale & shells	1155
salt & shale	1410
shale & shells	1516
lime	1915
lime sdy	1960
lime	1976
sand	2015
lime	2180
lime brkn	2347
sdv lime	2393
lime	2398
lime brkn	2515
lime sdy	2546
lime brkn	2810
lime	2846
shale	2885
lime	2936
shale & shells	2996
shale	3000
lime	3055
shale	3067
lime	3116
lime sft	3161
lime	3167
shale & shells	3189
lime	3290
shale	3305
lime & shale	3346
shale	3464
lime	3559
lime sft	3571
lime	3587
lime hd	3603
lime brkn	3659
lime	3672
lime sft	3681
lime	3768
lime & shale	3772
lime	3790
shale	3849
lime	3851
lime cored (rec. 2')	3855
lime & dolomite	3863
lime & chert	3871
Total Depth.	

Top Viola 3849
 Penetration 22

8-1-42 Halliburton drill stem
 test, packer at 3849, T.D.
 3855, open 30 min., made 30'
 rotary mud, no oil