

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

12-24-12 W

Company. DERBY OIL CO.
Farm. McKibben

No. 1.

SEC. 12
SEc NE

T. 24

R. 12 W

Total Depth. 4008

Comm. 10-11-44

Comp. 11-28-44


Shot or Treated.

Contractor. E. K. Carey

Issued. 2-10-45

County.

Stafford
KANSAS



Elevation. _____

CASING:
8 5/8" 325' Cem.
5 1/2" 4007' Cem.

Production. Pot. 290 B Pmp.
73 BW

Figures Indicate Bottom of Formations.

surface dirt & clay	0-15
sand	25
shale or clay	35
sand & shale strks	105
red rock	120
red rock & shells	175
red rock & sand	230
red rock	325
shale	385
red bed	608
anhydrite.	630
red bed	735
red bed, shale & shells	1145
shale & salt	1440
shale & shells	1460
shale & lime	1600
lime	1965
shale	2015
shale & lime	2690
shale	2755
shale & lime	2850
lime	3296
shale & lime	3369
shale	3412
lime & shale	3452
lime	3582
lime cherty	3608
lime	3741
shale & lime	3787
shale	3815
lime	3844
shale & lime	3861
cherty conglomerate	3873
lime	3917
lime cherty	3949
lime	3965
shale	4008
Total Depth	

Tops:

Lansing	3414
Viola	3824
Simpson shale	3964
Arbuckle	4001

Fair por & very lgt stain

3824-42. Good por no sat in
Arbuckle. DP to 3970 perf.

12/3818-26, 12/3822-26,

1000' oil no wtr 20 hrs.

500A Swab 14 BO no wtr 3 hrs

after swbg down. 2000A swab

18 BO no wtr hr 3 hrs after

swbg down. Comp. pump Pot.

290 BO 73 BW