

16-24-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STICKLE DRILLING
Farm- Mershon No.1

SEC. 16 T. 24 R. 12W
NW NE SE

Total Depth. 4112' (4115)
Comm. 3-18-63 Comp. 3-28-63
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 12-7-63

County Stafford
KANSAS



CASING:

Elevation. 1893' KB

8" 269' cme w/ 265 sx
5 1/2" 4114' cem w/ 150 sx

Production. 9 BOPD / 50% W

Figures Indicate Bottom of Formations.

sand & shale	165
shale & shells	271
red bed & shale	860
shale	1770
lime & shale	2010
shale & lime	2560
lime & shale	2790
shale & shells	3085
shale & lime	3217
lime	3360
shale	3385
shale & lime	3614
lime	3803
lime & shale	3890
lime	3908
lime & chert	3980
lime	4082
chert & lime	4087
Arbuckle	4105
lime	4112 RTD
Total Depth	

TOPS: LOG	
Anhydrite	692
Heebner	3331
Brown Lime	3482
Lansing Kansas City	3513
Kinderhook shale	3835 (3830)
Viola	3895
Simpson shale	4028
Simpson sand	4048
Arbuckle	4084 (4114)