


Company. STEARNS PETROLEUM, INC.
Farm- Byer No. 1

SEC. 21 T. 24 R. 12W
SW SW NE

Total Depth. 4135
Comm. 1-20-56 Comp. 2-6-56
Shot or Treated.
Contractor. Stearns Petroleum, Inc.
Issued. 4-14-56

County Stafford
KANSAS



CASING:
8 5/8 13 joints w/ 180 sx cmt.

Elevation. 1887 RB

Production. Dry

Figures indicate Bottom of Formations.

cellar	5
shale	25
sand & red bed	105
sand	135
shale	220
shale & shells	300
red bed & shale	375
red bed	720
anhydrite	740
shale & shells	1285
salt & shale	1420
shale & shells	1600
shale & lime	1650
lime	1680
lime & shale	2000
lime	2060
lime & shale	2090
lime	2160
lime & shale	2445
shale & shells	2800
shale	2810
lime & shale	3105
lime	3270
lime & shale	3570
lime	3758
shale & shells	3775
shale & lime	3815
shale	3850
shale & shells	3876
shale & lime	3905
shale	3923
lime	3954
lime & chert	3975
lime	4004
chert	4020
lime & shale	4023
lime	4038
lime & shale	4106
shale	4116
lime	4135
Total Depth	

TOPS:

Anhydrite	720
Heebner	3336
Toronto	3353
Brown lime	3491
Lansing-K. C.	3520
Base K. C.	3760
Kinderhook	3835
Viola	3923
Simpson shale	4032
Simpson sand	4069
Arbuckle	4116