


CONTINENTAL OIL CO.
G.V.Cline No. 1.

SEC. 30 T. 24 R. 12 W.
NW₄ SW
330' NL 330' WL SW₄

Total Depth. 4225 (Gr.L.4221)
Comm. 3-1-42 Comp. 3-19-42
Shot or Treated.
Contractor.
Issued. 5-2-42

County Stafford.



CASING.

103/4" 437' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

shale and sand	130
shale and shells	443
shale and red rock	750
anhydrite	770
shale and shells	1280
salt	1350
shale	1400
shale and shells	1635
shale and lime	1770
lime	1825
shale and lime	1860
broken lime	1940
lime	1950
shale and shells	2040
lime	2120
lime and shale	2240
broken lime	2305
shale and shells	2405
broken lime	2652
shale and shells	3010
broken lime	3050
lime	3164
shale and shells	3170
lime	3454
lime and shale	3560
shale and shells	3585
lime	3690
lime and chert	3720
lime	3907
cherty lime	3952
shale	4003
lime	4030
lime and chert	4110
broken lime and shale	4115
shale and lime	4160
lime and chert	4165
lime	4225 Total Depth.
	4221 Ground level
	Total Depth.

Top Viola 4003
Simpson 4102
Arbuckle 4160

Cored 4161-71 Rec. 2', r

y, no showing oil.