

Open 30", S.I. 45",  
Open 60", S.I. 60"  
Weak blow increasing to good blow  
Recovered 62' slightly oil cut mud,  
124' oil cut mud.  
ISIP 499# FSIP 400#  
FP 80-100# 100-120#

Computer Inventories

PI

McCoy Petroleum Corporation  
#1 Bartlett  
Drill Stem Tests

7-24-12W  
SE SW NE

DST #2 3636-3653' (L-KC)  
Open 30", S.I. 45", Open 60", S.I. 60"  
Weak blow, died in 50" on 2nd open.  
Recovered 30' gas cut oil specked mud.  
ISIP 1289# FSIP 1269#  
FP 40-60# 100-120#

DST #3 3702-3725' (L-KC)  
Open 30", S.I. 45", Open 60", S.I. 60".  
Weak blow throughout test  
Recovered 30' mud  
124' watery mud,  
124' watery mud with oil specks  
ISIP 1269# FSIP 1230#  
FP 40-80# 80-140#

DST #4 3740 - 3770' (L-KC)  
Open 30", S.I. 45", Open 60, S.I. 60"  
Weak blow throughout test  
Recovered 30' gas cut oil specked mud  
ISIP 993# FSIP 697#  
FP 40-80# 40-60#

DST #5 3767-3830' (Marmaton)  
Open 30", S.I. 45", Open 60", S.I. 60"  
Strong blow. Gas to surface in 6 minutes on 2nd open.  
Gauge 5860 CFGPD and stabilize  
Recovered 120' gas cut mud  
ISIP 1329# FSIP 1309#  
FP 60-60# 60-60#

DST #6 3872-3890' (Viola)  
Open 30", S.I. 45", Open 30", S.I. 45"  
Weak blow on 1st open. Dead on 2nd open.  
Recovered 30' mud  
ISIP 100# FSIP 100#  
FP 60-80# 40-80#

DST #7 3897-3940' (Viola)  
Open 30", S.I. 45", Open 90", S.I. 60"  
Strong blow. Gas to surface in 5 minutes.  
Gauge 33,900 CFGPD in 30" on 1st open,  
Gauge 33,900 CFGPD in 10" on 2nd open,  
surging and decreasing to 1,680 CFGPD in 90".  
Recovered 1431' of fluid as follows:

563' clean gassy oil, )  
713' froggy oil, ) 1276' oil  
155' oily muddy water

ISIP 618# FSIP 894#  
FP 240-419# 439-537#

AUG 0 1 1985

State Geological Survey  
WICHITA BRANCH

PI

7-24-12w

DST #8 3940-3965' (Viola)  
Open 30", S.I. 45", Open 60", S.I. 60"  
Steady 2" blow throughout test.  
Recovered 124' of oil and gas cut mud.  
ISIP 598# FSIP 598#  
FP 60-80# 60-80#

DST #9 3990-4053' (Simpson)  
Open 30", S.I. 45", Open 30", S.I. 45"  
Weak blow on 1st open. Dead on 2nd open.  
Recovered 30' of very slightly oil and gas cut mud.  
ISIP 120# FSIP 80#  
FP 60-60# 60-60#

AUG 0 1 1985

State Geological Survey  
WICHITA BRANCH