

4-24-13W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CROWN OIL CO., INC.
Farm - Glasscock No. 1

SEC. 4 T. 24 R. 13W
NE NE NE

Total Depth. 3940
Comm. 11-23-49 Comp. 12-9-49
Shot or Treated.
Contractor. Hilton Drilling Co.
Issued. 10-7-50

County. Stafford
KANSAS



CASING:
8 5/8" 331' cem w/200 sx.
5 1/2" 3938' cem w/100 sx.

Elevation. 1906 DF

Production. 60 bbls oil and
30 bbls wtr.

Figures Indicate Bottom of Formations.

surface soil, sand	150
shale, shells, red bed	245
shale sdy	405
red bed	770
anhyd.	800
shale, shells	1625
lime, shale	1635
lime	1945
lime brkn, shale	2080
lime	2215
lime, shale	2575
shale, shells	2715
lime, shale	3015
lime	3430
lime, shale	3530
lime	3830
lime, chert	3885
shale	3897
lime	3940
Total depth	

Tops:
Heebner shale 3340
Lansing white 3520
Viola 3824
Simpson 3880
Arbuckle 3936

Remarks:
3526-34, soft xlyn and oolitic lime, to
spotted oolitic; no show no odor.
3544-50 and 3574-57, same as above.
3673-80, wht med oolitic lime, good
porosity, trace lgt spotted stain, good
odor, possible gas odor.
3692-3700, spotted oolitic and vugular
porosity, slight odor, poor spotted stain.
DST 3673-80, 3692-3700 run from 3671-3702,
(31' anchor) the test produced a strong blow
during the 25 mi open period. Rec. amounted
to 250' oil and gas, and heavily gas cut mud.
Closed in BHP.

ALL MEASUREMENTS FROM KELLY BUSHING: