

6-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HILTON DRIG. CO., INC.
Farm- Rusmiser No. 1

SEC. 6 T. 24 R. 13W
NW NW NW

Total Depth. 4117
Comm. 11-12-51 Comp. 11-30-51
Shot or Treated.
Contractor. Hilton Drig. Co. Inc.
issued. 12-29-51

County Stafford
KANSAS



CASING:

8 5/8" 223' cem w/250 sxs.

Elevation. 1905 DE
1907 (2nd)

Production. dry

Figures Indicate Bottom of Formations.

surface sand, clay	223
red bed, shells	280
sand	315
red bed, shells	780
anhydrite	810
shale, shells	1275
shale, shells, salt	1410
lime, shale	1685
lime	2152
broken lime	2240
lime, shale	2990
lime	3510
lime, shale	3543
lime	3915
conglomerate, chert	3970
cherty conglomerate	4018
chert, lime	4035
cherty conglomerate	4055
shale, sandy dolomite	4085
shale, dolomite, lime	4112
lime	4117
Total depth	

Tops:	
Heebner	3409
Lime Brown	3538
Lansing	3570
Conglomerate	3856
Viola	3941
Simpson	4050
Arbuckle	4100