

7-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Henderson No. 1

SEC. 7 T. 24 R. 13W  
NW NW SE  
2310' FEL, 2310' FSL

Total Depth. 4176'  
Comm. 2-9-56 Comp. 2-24-56  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 5-19-56

County Stafford  
KANSAS



CASING:

8 5/8" 229' ccm w/200 sx  
5 1/2" 3930' ccm w/100 sx

Elevation. 1924' DE

Production. 1393 BOPD

Figures Indicate Bottom of Formations.

clay, sand & gravel	75	
sand & gravel	145	
shale, shells & red bed	229	
shale, red bed, sand	816	
anhydrite	835	
shale & shells	1400	
shale & lime	1770	
lime	1940	
lime & shale	2425	
shale & shells	2610	
shale & lime	3000	
shale & shells	3160	
shale & lime	3310	
lime	3375	
shale & lime	3479	
shale, lime, shells	3575	
shale & lime	3620	
lime	3864	
cherty lime & shale	3937	
conglomerate	3995	
chert	4021	
cherty lime & shale	4051	
chert	4121	
shale & lime	4173	
Arbuckle	4176	RTD
Total Depth		

Tops:	
Topeka	3101
Heebner	3409
Douglas	3448
Brown Lime	3543
Lansing	3572
Base Kansas City	3832
Viola	3970
Simpson	4093
Arbuckle	4150