

7-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INC.
Farm. Henderson No. 2

SEC. 7 T. 24 R. 13W
NW SW SE

Total Depth. 4193
Comm. 7-16-56 Comp. 7-28-56
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 9-15-56

County Stafford
KANSAS



Elevation. 1926 DF

Production. 326,000 CFGPD

CASING:

8 5/8 @ 229' w/ 200 sx cmt.
5 1/2 @ 3960' w/ 100 sx cmt.

Figures Indicate Bottom of Formations.

sand	110
blue shale	160
shale	260
red bed & sand	820
anhydrite	842
shale & shells	1900
lime & shale	2145
lime	2340
shale & lime	2685
shale & shells	3010
lime & shale	3195
lime	3410
shale & sand	3525
lime & chert	3655
lime	3850
lime & chert	3903
shale	3908
chert	3974
lime & shale	3997
chert	4057
lime	4107
shale & sand	4161
lime	4169
Arbuckle	4193
Total Depth	

TOPS:	
Anhydrite	820
Heebner	3409
Toronto	3431
Brown lime	3544
Lansing	3574
Base KC	3835
Mississippi	3886
Kinderhook	3979
Viola	3990
Arbuckle	4163