

8-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- McConnaughay No. 1

SEC. 8 T. 24 R13W
SW SW NW

Total Depth. 4143'
Comm. 6-25-60 Comp. 7-7-60
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 6-17-61

County Stafford
KANSAS



CASING:
8 5/8" 265' cem w/225 sx.
4 1/2" 3900' cem w/150 sx.

Elevation. 1928' KB

Production. 50 BOPD

Figures Indicate Bottom of Formations.

sand	45
sand & gravel	220
red bed & shale	265
red bed	810
Anhydrite	830
shale & shells	1720
lime & shale	2080
lime	2250
lime & shale	2430
shale & lime	3290
lime	3372
lime & shale	3475
shale & lime	3624
lime	3867
shale & cherty lime	3910
lime & dolomite	3960
lime	4008
cherty lime	4065
lime, shale & sand	4107
Arbuckle lime	4143
Total Depth	

TOPS: SCOUT	
Heebner	3412
Toronto	3433
Douglas	3450
Brown Lime	3551
Lansing	3576
Base Kansas City	3837
Viola	3937
Simpson Shale	4075
Simpson Sand	4095