


CONTINENTAL OIL CO.
J. Holmes No. 1.

SEC. 9 T. 24 R. 13 W.
SEc SE
330' fr S & E Lines SE $\frac{1}{4}$

Total Depth. 4118 (G.L. 4116)
Comm. 11-25-41 Comp. 12-16-41
Shot or Treated.
Contractor.
Issued. 4-4-42

County Stafford.



CASING.

103/4" 437' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

sand	80
clay and gravel	187
shale and shells	444
red rock	552
shale and shells	748
anhydrite	780
shale and shells	1320
salt	1350
shale and shells	1620
lime	1820
lime and shale	1980
shale	1990
shale and shells	2050
sand	2080
broken lime	2130
sand	2140
broken lime	2530
shale and shells	2825
broken lime	2835
shale and shells	2880
sand and lime	2897
lime and shale	2915
shale and shells	3060
shale	3100
lime	3185
lime and shale	3280
shale and lime	3345
lime	3455
shale	3505
shale & shells	3535
lime	3611
shale breaks	3620
lime	3865
lime and shale	3935
chert and lime	4025

shale and lime 4088
lime 4118 Total Depth
Total Depth from Ground level 4116

TOPS
Kansas City 3545
Viola 3887
Arbuckle 4081

Cored from 4086-96
Rec 5' of Arbuckle lime, no Saturation
slight odor of sulphur.
Cored 4096-4116
Rec 3' of Arbuckle lime, no show of
oil, but strong odor of Sulphur