

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

12-24-13W

Company GRAYBOL CONTRACTING CORPORATION &
Farm- Garner No. 1 L. B. SMITH

SEC. 12 T. 24 R. 13W
NW SW NW

Total Depth. 4067

Comm. 5-7-53

Comp. 5-22-53


County Stafford

KANSAS

Shot or Tested.

Contractor Graybol Contracting Corporation

Issued. 8-8-53



CASING:

8 5/8 242' w/ 175 sx cement

Elevation. 1902 RB

Production. Dry

Figures Indicate Bottom of Formations.

sand & gravel	160
red rock, shale & shells	242
shale & shells	280
red bed	740
anhydrite	765
shale & shells	1370
lime & shale	1730
sandy lime & shale	1790
lime & shale	1840
sandy lime & shale	2110
lime & shale	2165
shale	2240
lime & shale	2855
shale	2880
lime & shale	3024
lime & shale streaks	3354
shale	3359
lime	3363
shale & red shale	3379
lime	3399
shale, red & green-gry	3494
brown lime	3501
shale	3521
lime & shale streaks	3767
shale & lime	3831
conglomerate	3846
chert & shale	3948
dolomitic lime, shale & lime	3968
dolomite	3998
sand, shale grn, sly shale	4035
crystalline dolomite	4067
Total Depth	

TOPS (RB)

Topeka	3024
Heebner	3354
Toronto	3379
Douglas	3390
Brown lime	3494
Lansing	3521
Conglomerate	3831
Viola chert	3846
Simpson	3968
Arbuckle	4035

DST #1: 3544-99, open 1 hr. rec.
90' mud w/ few specks oil. BHP 810#

DST #2: 3850-88, open 20 min. rec.
10' mud, BHP 0#

DST #3: 3970-4002, open 50 min. rec.
20' mud w/ few specks dead oil, 60'
watery mud. BHP 170#