

17-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- Harrison "B" No. 1

SEC. 17 T. 24 R. 13W
NE SW SW

Total Depth. 4210'
Comm. 5-10-58 Comp. 5-23-58
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 4-11-59

County Stafford
KANSAS



CASING:
8 5/8" 246.77' cem w/200 sx.
5 1/2" 3990' cem w/150 sx.

Elevation. 1932' DF

Production. 76 BOPD

Figures Indicate Bottom of Formations.

surface soil & sand	45
sand & shale	247
shale & shells	800
Anhydrite	835
shale & shells	1785
shale, shells & lime	2000
lime	2200
shale & lime	3350
lime & shale	3578
lime	3905
chert	3920
shale	3975
lime	4000
chert	4037
cherty lime	4094
chert	4124
lime & shale	4165
Arbuckle lime	4210
Total Depth	

TOPS: SCOUT	
Anhydrite	800
Heebner	3424
Toronto	3449
Douglas	3469
Brown Lime	3567
Lansing	3592
Base Kansas City	3848
Conglomerate	3886
Mississippi	3897
Kinderhook	3909
Viola	3981
Simpson	4136
Simpson Sand	4145
Arbuckle	4181